

DIVISION 31 - EARTHWORK

31 10 00 SITE CLEARING

31 11 00 CLEARING AND GRUBBING

- 1 Direct contractor to comply with the requirements of the soil erosion control permits and specifications.
- 2 Conform to all local, state and federal regulations relating to environmental requirements, disposal of debris and use of herbicides.
- 3 The excavator shall install temporary stakes, at least four (4) feet in height above anticipated finish grade to mark sanitary, storm, electrical and telecommunications manholes, irrigation control valves; domestic and fire protection water shut-off valves. The top 12 inches of the stake shall be painted according to the color schedule below. Stakes shall be wood or metal and shall be installed in a manner to insure the upright position thru the course of construction. Stakes removed, damaged or knocked over shall be immediately replaced. Stakes are to be pulled after topsoil and fine raking are completed and hydro-seed or sod is placed.
 - A Sanitary manholes: Black
 - B Storm Water Manholes: Light Blue
 - C Irrigation Control: Green
 - D Domestic Water Shut-off: Dark Blue
 - E Fire Protection Shut-off: Red
 - F Electrical/Telecommunications manholes: Yellow

31 14 00 EARTH STRIPPING AND STOCKPILLING

31 14 13 SOIL STRIPPING AND STOCKPILLING

- 1 Excess excavated soil materials shall be removed from the construction site and campus property.

END OF SECTION