KOODS **AUTOMATION SYSTEMS**

Pre-design

Koops' current conduction-based thermal manufacturing process has a high part to part cycle time of 75 to 90 seconds, with 20-30 seconds of heating and 20-30 seconds of cooling time per part typically. The aim of this project is to utilize IR and active cooling to reduce the part-to-part cycle time by 30%. To be considered a definite improvement, due to changes in geometry for the test station compared to the true machine, heating and cooling times of less than 8 seconds, or a combined total of less than 16 seconds were required. For a likely improvement, combined times of 22 seconds or less were required.



nights Banquet from left: Nik Short, Camryn Lozon, Briar Koelzer, Matt Pavlock, Emily Battey, and Prof. Philip Hittepole.



The Team at work, building the machine

Two heating methods were compared for this project. The previous method used by Koops, conduction heating, was tested utilizing a test station (right) that Koops already possessed. An IR test station had to be designed for comparison to conduction cycle times. For IR, bulb distance, bulb power, and heating and cooling times all play a role in the effectiveness of the finished product. Unlike IR, for conduction the main factors which affect performance are limited to heat and cool times.

Key Specifications

- •Maximum budget: \$12,000
- Test station temperature range: 370 °F 700°F
- Maximum test station size: 5' x 5' x 5'
- Minimum sample size: 6" x 6"
- Must provide IR and conduction heating
- calculations and heating data
- Test station must allow for testing to help reduce thermal manufacturing process cycle time

• Design and build IR test station to help Koops achieve a decreased cycle time Perform experiments using test station to analyze cycle time feasibility for both conduction and infrared heating

Functional Requirements:



Koops Thermal Manufacturing Process Cycle Time Improvement Group Members: Emily Battey, Brian Koelzer, Camryn Lozon, Matt Pavlock, and Nik Short


Faculty Advisor: Prof. Philip Hittepole

 Design and build functional IR test station to provide data on heating and cooling times for several different materials

 Perform heat transfer analyses and experiments on feasibility of IR and conduction heating methods




Conduction Test Station



Thermal Imaging Photos

Mechanical Design of IR Test Station





Results and Analysis IR vs. Conduction

Vortex cooling results were less When the bulb was placed closer to was able to reach desired IR effective than anticipated for decreasing temperatures in the 4 to 7 second the part, average recorded temperature temperature but were an improvement range, while Conduction took closer to increased significantly for the upper over conduction results. Vortex cooling 10 to 15 seconds. As expected, 90% IR surface. Parts heated at 10 mm often created a more effective final product power heated faster than 75%, with up exhibited charring, but parts at 20 and with lower effective cooling times. to a 200 °C difference in some tests. 30 mm proved promising for cycle time reductions.

	Material 1	Material 2	Material 3
Heat time (s)	6	8	15
Cool Time (s)	5	10	5

The IR test station was designed to be as similar as to the previous possible conduction station. The tooling itself is confidential, but the overall design includes table space for sample storage and a mounting table for ease of use.

The HMI and Estop were mounted to the electrical cabinet.



Final Build Photos of Test Station


Controls Design of IR Test Station


IR bulb Schematic

The bulb was selected to achieve part temperatures of 700 °F or 370 °C


Bulb Power is controlled by a variable voltage heater controller, through analog outputs on the PLC.

The PLC selected was an 1769 L18ER-BB1B (right), which Koops had in stock.





10 vs. 20 vs. 30 mm IR heating results



After final testing, materials 1, 2, and 3 achieved combined cycle times of 11, 18, and 20 seconds, respectively. This indicates that IR would most likely be successful in reducing cycle time on a full machine.


• Build was completed under-budget •Test station size was within limits • Test station accommodates samples larger than 6" x 6"

Vortex tube utilized for cooling

Vortex tube compressed air cooling was tested to try to reduce cooling times.

PLC, HMI, and remote I/O selected for this application

HMI The was designed allow to change easy of parameters, including cooling time, heating time, and bulb power. The program sequence was made as similar as possible to the conduction station, for consistency.



0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29